

LEGEND	
	PROPOSED HOUSE
	WATER
	SANITARY SEWER
	STORM DRAIN
	EXISTING CONTOURS
	PROPOSED CONTOURS
	PROPERTY LINE
	SILT FENCE
	STABILIZED CONSTRUCTION ENTRANCE & WHEEL CLEANING BLANKET
	EXISTING TREE TO REMAIN
	TREE TO BE REMOVED
	TREE TO BE PLANTED
	I.P. IRON PINS



NOTE:
SLATE PATIO AND WALKWAYS
TO BE REMOVED AS PER THE
2010 SUBDIVISION PLAN

66.21-1-41.1
SFR-1


66.21-1-43
SFR-1

66.21-1-41.2

66.21-1-40
SFR-1



STONE WALL DETAIL
SCALE 1/2" = 1'-0"



2 LOCATION MAP
SP-1 N.T.S.



3 VICINITY MAP
SP-1 N.T.S.

Drainage Design: 124 Fifth Soils-Wethersfield "C"			
Development size =	0.0514 Acre		
Undeveloped SCS Curve No. =	74.0000		
Developed SCS Curve No. =	98.0000		
1. Select Design Storm			
100 year, 24-hour			
2. Type of subsurface disposal system:			
Concrete drywell			
3. Determine Percolation Rate:			
Percolation Rate:			
Drop	1.0000 inches		
Time	30.0000 minutes		
a. Area of Percolation (Ap):			
Surface area of Cylinder			
Ac=Pi*Dhavg			
D=	1.0000 foot		
havg=	9.5000 inches		
Ac=	2.4871 Ft*2		
Bottom Area			
Ab=Pi*r*2			
Ab=	0.7854 Ft*2		
Volume of Percolation:			
Ap=Ac+Ab			
Ap=	3.2725 Ft*2		
Vp=Ab*h			
Soil Percolation Rate			
Sr=volume/area/time			
Sr=	0.0007 Ft*3/Ft*2/Min.		
Sr=(minus clogging factor of 25%)			
Sr=	0.9600 Ft*3/Ft*2/day		
Sr=	0.7200 Ft*3/Ft*2/day		
4. Calculate Required Storage Volume:			
100yr, 24 hour rainfall=	9.3000 inches		
From Table 2-1 of TR-55			
Existing CN=	74.0000 therefore depth Vr=	6.11 Inches	
Proposed CN=	98.0000 therefore depth Vr=	9.10 Inches	
DeltaVr=	2.9900 Inches		
Vs=deltaVr*Area			
Vs=	558.1333 Ft*3		
5. Calculate Volume per Drywell:			
Vw=Pi*r*2*height			
Thickness of Stone=	2.0000 feet		
Thickness of drywell wall=	0.3330 foot		
Diameter of drywell=	6.0000 feet		
Height of drywell=	6.0000 feet		
Vw=	254.7120 Ft*3		
6. Calculate 24-hour percolation volume per drywell(Vp):			
Vp=bottom surface area of drywell*soil percolation rate(Sr)			
Vp=Pi*D*h*Sr			
Vp=	64.3318 Ft*3/day/drywell		
*Note: Sides of drywell not included			
7. Calculate the total 24-hour Volume per drywell (Vt):			
Vt=Volume of drywell(Vw)/percolation volume(Vp)			
Vt=	319.0437 Ft*3		
8. Determine number of drywells required (DWr):			
DWr=Req. Volume of Storage(Vs)/Total Vol. per Drywell(Vt)			
DWr=	1.7494		
USE		2	

TABLE 4-1 DIMENSIONAL STANDARDS OF THE VILLAGE OF NYACK ZONE SFR-1		
	REQUIRED	PROPOSED
MINIMUM LOT AREA	7,500 SF	7,500 SF
MINIMUM LOT WIDTH	50'	63.5'
FRONT SETBACK	23.6'	31.5'
SIDE SETBACK	6.35'	8.0'
SIDE SETBACK (BOTH)	19.05'	25.3'
REAR YARD	35.43'	40.5'
MAXIMUM BUILDING HEIGHT (STORES)	2	2
MAXIMUM BUILDING HEIGHT (FEET)	32'	27'
MINIMUM USABLE AREA	1,500 SF	2,525 SF
OFF STREET PARKING D.O.	2	2
MINIMUM DWELLING SIZE	900 SF	2,525 SF

CHART OF SETBACKS	
FRONT	20% OF LOT AREA DIVIDED BY LOT WIDTH = .20x7500 / 63.5 = 23.6'
SIDE	5 FEET OR 10% OF LOT WIDTH = .10x63.5 = 6.35'
SIDE (BOTH)	30% OF LOT WIDTH = .30x63.5 = 19.05'
REAR	30% OF LOT AREA DIVIDED BY LOT WIDTH = .30x7500 / 63.5 = 35.43'

DO NOT SCALE PRINTS

REVISIONS:	
DATE:	16 FEB 2026
SCALE:	AS NOTED
SHEET:	SP-1

REVISIONS:	
DATE:	04 MAY 2026
SCALE:	AS NOTED
SHEET:	SP-1

REVISIONS:	
DATE:	16 FEB 2026
SCALE:	AS NOTED
SHEET:	SP-1

REVISIONS:	
DATE:	04 MAY 2026
SCALE:	AS NOTED
SHEET:	SP-1

REVISIONS:	
DATE:	16 FEB 2026
SCALE:	AS NOTED
SHEET:	SP-1

REVISIONS:	
DATE:	04 MAY 2026
SCALE:	AS NOTED
SHEET:	SP-1

REVISIONS:	
DATE:	16 FEB 2026
SCALE:	AS NOTED
SHEET:	SP-1

REVISIONS:	
DATE:	04 MAY 2026
SCALE:	AS NOTED
SHEET:	SP-1